Stettler Single Mailbox Stand: Constructed entirely of Western Red Cedar

8 ft long 6 x 6 post, with 2 dado cuts around the top of the post terminating into a flattened wood pyramid. All cedar.

It has an approximate 36" long mailbox support arm made from 2" x 8" lumber. All made of cedar.

The cedar newspaper box an approximate dimension of 6" x 6". Top board of newspaper box is approximately 24" long and approximately 11 ½" wide. Again, all cedar construction.

The Stettler Single Mailbox Stand is identical to the Stettler Single Stands you currently have.

Stettler Twin Mailbox Stand (for 2 homes): Constructed entirely of Western Red Cedar

8 ft long 6 x 6 post all cedar, with 2 dado cuts around the top of the post terminating into a flattened wood pyramid.

The double mailbox armset/platform is approximately 36" wide and the side arm pieces are also 36". It is entirely made of cedar.

The two cedar newspaper boxes each have approximate dimension of 6" x 6". Top board of each newspaper box is approximately 24" long and approximately 11 ½" wide. All cedar construction.

The Stettler Twin Mailbox Stand is identical to the Stettler Twin Stands you currently have.

Stettler Triple Mailbox Stand (for 3 homes): Constructed entirely of Western Red Cedar

Two - 8 ft long 6 x 6 posts all cedar, both with 2 dado cuts around the top of the post terminating into a flattened wood pyramid.

The triple mailbox armset/ platform is approximately 55 ¼"" wide and the side arm pieces are also 36". It is entirely made of cedar.

The three cedar newspaper boxes each have approximate dimension of 6" x 6". Top board of each newspaper box is approximately 24" long and approximately 11 ½" wide. All cedar construction.

The Stettler Triple Mailbox Stand is identical to the Stettler Triple Stands you currently have.

Black Newport Steel Mailboxes with Red Steel Flags

Made with US Steel, entirely made and assembled in the USA.

Dimensions: Approximately 8.7" wide x approximately 11" high, x approximately 22.6" deep.

Each box has a full piano hinge attaching the door to the mailbox cylinder. It has door gasketing.

Each box has a plastic tray to keep mail raised in the interior of the mailbox.

Vinyl Lettering:

Each single mailbox stand will have 3" cream-colored vinyl numbering in Baskerville font.

The boxes will also have front 1.25" vinyl numbers.

Each end box on a twin stand will have 3" vinyl numbers on the far outsides of the stand, and each mailbox will have 1.25" front vinyl numbers.

Each end box on a triple stand will have 3" vinyl numbers on the far outsides of the stand, and each mailbox will have 1.25" front vinyl numbers.

Metal Bands – These are black vinyl clad aluminum bands approximately 6" x 6" x 6" that wrap the base of each post.

Mailbox installation and old stand removal:

We will be removing and disposing of all the old mailboxes and stands.

Each new stand will be installed approximately 32" to 36" deep in the ground, depending on the slope of the land. The mailbox platform will be installed at the USPS specified height.

Each hole has differing moisture and soil content. We will be adding class 5 gravel, or dry cement to the holes that have excess moisture as needed. This will be entirely up to the installers.

Because we are digging, we will do our best to not disturb flowers, but we cannot guarantee how they will react to our disturbing the area. We will not replace any plants. The same applies to trees & bushes.

Our installers are full time employees that have been doing this for thirty years and they have done the North Saunders Lake Development twice, and your original development at South Saunders Lake and now this second installation at South Saunders Lake. We will do a professional job.

The posts will be stained in 2021 to allow the cedar to properly dry out. Outdoor Designs recommends Sikkens Log & Siding Stain in Butternut.

Thank you again for your continued confidence in Outdoor Designs & Service

Subject to correction if any typographical errors.